BRUHATH BENGALURU MAHANAGARA PALIKE

Yelahanka Division, Yelahanka Zone

Executive Engineeer
Yelahanka Division
B.B.M.P. Bengaluru - 64
No:EE/YNK-D/E-PMT/07/2016-17 Dated: 27-02-2017

APPROVED TENDER SCHEDULE –'B'

Item No: 19

Name of Work:- Repairs to Samuadaya Bhavana and Providing WPC to Gov School at Yelahanka 4th phase in Attur ward No 03

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri U RAMESH	
				Rate	Rate in Words
1	Dismantling of existing structures like culverts,bridges, retaining walls and other structure comprising of masonry, cementconcrete, wood work, steel work, including T&P and scaffolding wherevernecessary, sorting the dismantled material, disposal of unserviceablematerial and stacking the serviceable material with all lifts complete asper specifications Dismantling brick/Tile work B. In cement mortar.(p.no,137/ si,no18.18,PWD SR 2016-2017)	Cum	1.08	400.00	Rupees four hundred only
2	KSRRB 300-1,Earth work excavation by manual means in ordinary soil involving an average horizontal throw up to 2 meters and an average lift uo to 1.5m,excavated surface levelled and sides neatly dresssed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications (Item no19.1,Page no141, PWD SR 2016-17)	Cum	28.00	88.00	Rupees eighty eight only
3	KSRRB M100-1 Loading and un loading of stone boulder/Stone aggregates/ sand/kanker/ Moorum.KSRRB M100-1:Placing tipper at loading point,loading with front end loader,dumping,turning for return trip,excluding time for haulage and return trip complete as per specifications(Item no17.1,Page no130,PWD SR 2015-16	Cum	28.00	73.00	Rupees seventy three only
4	KSRB 4-1.3:Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @180kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed,machine mixed,concrete laid in layers not exceeding 15cms.thick, well compacted in foundation,including cost of all materials,labour,HOM of machinery,curing complete as per specifications.Specification no KBS4.1,4.2(Item no 4.3,Page no12,PWD SR 2016-17)	Cum	9.75	5256.00	Rupees five thousand two hundred fifty six only

Chief Engineer (Yelahanka -Zone) for kind information
2 Assistant Executive Engineer, Yelahanka

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri U RAMESH	
				Rate	Rate in Words
5	KSRB 4.2.2 : Providing and laying in position Reinforced cement concrete of design mix M20 with OPC cement @ 320kgs, with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.460cum with superplastesisre @ 3lts conforming etc as per specification&direction of the engineer incharge of work (pwd sr2016-17,p.no13,sno4.11)	Cum	1.08	6491.00	Rupees six thousand four hundred ninety one only
6	KSRB 4.9.2: Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per specifications.Specification noKBS 4.6.3,TMT bars Fe55 0(pwd sr2016-17,p.no17,s.no4.46)	Tonne,s	0.10	61237.00	Rupees sixty one thousand two hundred thirty seven only
7	KSRB 4-6.4 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, attached pilasters, bittresses,buttresses plinth and string course including cost of all materials,labour complete asperspecificationS.Specification no.KBS 4.6.2 (pwd sr2016-17 p.no15/4.31)	Sqm	6.82	316.00	Rupees three hundred sixteen only
8	KSRB M2200-5.11.Design mix M20 with OPC cement @320 kgs,with 20mm and down size graded granite metal coarse aggregates @0.69cum and fine aggregates @0.460cum with superplastesisre @ 3lts conforming to IS9103-1999 Reaffirmed-2008.etc as per specification&direction of the engineer incharge of work (pwd sr2016-17,p.no216,sno28.7.9)	Cum	11.68	7723.00	Rupees seven thousand seven hundred twenty three only
9	KSRB 5-14: Providing and constructing precast concrete solid blocks with compressive strength not less than 35Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications. (P25/5.27)	Sqm	33.78	1011.96	Rupees one thousand eleven and paise ninety six only
10	5 mm thick plain glass(P.no XIII/S.no371 PWD SR 2016-2017)	Sqm	23.22	700.00	Rupees seven hundred only
11	KSRB 7.90:Providing and fixing MS grill work for windows and ventilators using MS flats,or Square rods,or Combination of M.S Flats and Square rods as per approved design,drawing including as per specifications and directions of the engineer in charge of the work.(p.no32/s.no7.90,pwd sr 2016-2017)	Kg,s	717.60	76.50	Rupees seventy six and paise fifty only
12	Providing 12mm thick cement plaster in single coat with cemert mortar 1:3, to **ceiling** including rounding off corners wherever required smooth rendering,, Providing and removing scaffolding, including cost of materials, labour, lead, lift, curing complete as per specifications and direction of the Engineer in charge Providing Lime rendering for Plastering to Ceiling including cost of materials, labour, curing complete as per specification	Sqm	5.20	195.00	Rupees one hundred ninety five 'only

	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri U RAMESH	
				Rate	Rate in Words
13	Providing 18mm thick cement plaster in single coat with cement mortar 1:4, to brick masonry including rounding off corners wherver required smooth rendering, : Providing and removing scaffolding, cost of materials, labour, curing complete as per specifications and direction of the Engineer in charge Providing lime rendering for plastering to wall and ceiling including cost of materials labour curing complete as per specifications **Internal** wall plastering	Sqm	43.84	238.00	Rupees two hundred thirty eight 'only
14	Providing 18mm thick cement plaster in single coat with **cement mortar 1:6,** to brick masonry including rounding off corners wherver required smooth rendering, : Providing and removing scaffolding, cost of materials, labour, curing complete as per specifications and direction of the Engineer in charge.for **Outside Plastering**	Sqm	18.00	213.00	Rupees two hundred thirteen 'only
15	Providing and applying painting in two coats with **plastic Emulsion paint** of approved brand on ceiling surface to give an even approved shade after thoroughly brushing the surface, free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications and as per the directions of the Engineer in charge.**with primer**	Sqm	396.00	48.00	Rupees forty eight only
16	Providingexternalwallswithtextureingapprovedbrandpaint,applieduniformlyinthreecoatsoveronecoatofprimerincludingcostofallmaterials,machineries,labour,transportation,loading&unloading,allleadandliftandotherincidentalchargesincludingscaffoldingandremovingstains,completeasperspecification.(P125/15.103)	Sqm	330.00	311.00	Rupees three hundred eleven only
17	KSRB 7.1: Providing and fixing inposition collapsablesteelshutterswithsingleordoubleleafwithverticalchannel20mmx10mmx2mm braced with flat iron diagonals 20mmx5mm size, with top and bottom rails of T iron sections of 40x40x6mm with 38mm dia steel pulleys complete with bolt and nuts, locking arrangements, stopers, handles on borht sides with 7.5cms opeinings at 10cms. c to c applying a priming coat of red lead paint. cost of materials, labour, HOM of machinery complete as per specifications.(P31/7.1)	Sqm	5.04	4355.00	Rupees four thousand three hundred fifty five only
18	Applying priming coat over new wood surface and/ or wood based surface after preparing the surface after throughlycleaning oil, grease, dirt and foreign matter, sand papering and knotting liquid wood filler, for varnish including cost of materials, labour, completeas per specifications.	Sqm	108.14	44.28	Rupees fourty four and paise twenty eight only
19	Providing and Applying painting two coats (excluding priming coat) on new wood surface and / or wood based surface with enamel paint to give an even shade, clening the surface of all dirt, dust and foreign matter, sand papering including cost of materials, labour, complete as per specifications (P No. 102 Item No.15.60.1 PWD SR 2016-17)	Sqm	108.14	90.00	Rupees ninety only

Sl	Description	Unit	Approved Qty	Rate Quoted by the Contractor Approved Rates Sri U RAMESH	
				Rate	Rate in Words
20	KSRB13-1.1 : Providing and fixing to wall, ceiling and floor galvanised/mild steel tube 20 mm dia nominal bore with fittings (medium grade weight 1.27 kg/mtr) B class including cost of all materials, labour charges, HOM of equipments and testing complete as per specifictaions. Specification No. KBS 13.2.14/13.8. (P-90 & 13.1).	M	12.00	241.00	Rupees two hundred forty one only
21	KSRB 13-6.1-1 : Providing and fixing in position brass bib cock of approved quality 25 mm nominal bore including cost of all materials, labour and HOM of equipments with all leads, complete as per specifications. Specification No. KBS 13.2.2/13.3 (Page No. 80 & Item No. 13.23).	Each	4.00	293.00	Rupees two hundred ninety three only
22	Supplying water storage tanks made of virgin polymer (LLDPE) with two layers outer black or Blue and inner white layer of approved quality and make, conforming to I.S.I/ISO/SSI specifications.	Ltr.	2000.00	2.00	Rupees two only
23	Urocon tiles(Approved data rate)	Sqm	24.00	1500.00	Rupees one thousand five hundred only

U Ramesh
Signature of the Contractor

Executive Engineer,
Yelahanka Division,
BBMP, Bengaluru-64.